

June 27, 2014

Æ No. 14-5164-712

Mr. Steve Bojkovic
1311 Cook Street
Denver, Colorado 80206

Subject: ASBESTOS SURVEY
Holland Drive (former) Sunoco
Swartz Creek, Michigan

Dear Mr. Bojkovic:

Mr. Michael Smith, a Michigan Accredited Asbestos Building Inspector (Accreditation Number A33883) of Applied *Eco*Systems, Inc. (Æ), performed an asbestos demolition survey of the above-referenced building.

The following suspect materials were identified and sampled in accordance with the Michigan Department of Environmental Quality (MDEQ) National Emission Standards for Hazardous Air Pollutants (NESHAP) guidelines.

The collected samples were shipped using proper chain-of-custody to CEI Labs, Inc., for analysis of asbestos content using Polarized Light Microscopy (PLM). The samples were analyzed under a “stop at first positive” procedure. Results are as follows:

Sample No.	Description	Asbestos Content
1	Ceiling tile	ND
2	Vinyl baseboard (black)	ND
3	Floor tile – cashier area	2%
4	Window caulk	ND
5	Vinyl baseboard (tan)	ND
6	Ductwork vibration dampener	ND

ND = Not Detected

During demolition or renovation activities, the possibility exists that additional suspect materials could be encountered, such as cloth electrical wire enclosed in conduits, concealed roofing, insulation inside concrete block cavities and other situations where a full assessment cannot be completed without significant damage to the building or building components. In the event that suspect materials are encountered during renovation or demolition, a certified inspector should be consulted.

MATERIALS REQUIRING ABATEMENT

- The floor tile (but not the mastic) located in the cashier area tested positive for asbestos and should be removed/disposed properly.

A copy of the asbestos analytical report is attached. Should you have any questions, please do not hesitate to contact me at (810) 715-2525.

Sincerely,

APPLIED *Eco*SYSTEMS, INC.



Michael D. Smith
Project Manager

MDS:lm

Attachments